



Item 7.2 refix loose stone to crenellation



Item 7.12 provisionally allow to remove and refix stone piece

Item 7.3, 7.3.1 rewedge and repoint missing pointing



Notes:

1. This drawing is to be read in conjunction with all Architect's drawings and Specification and all relevant contract documentation.
2. Drawings must not be scaled. The contractor is to verify all dimensions and details on site, and is to report any discrepancies to the architect immediately.
3. The contractor is to carry out everything necessary for the proper execution of the works whether or not shown on the drawings or described in the Specification provided the same may reasonably be inferred therefrom.
4. All work is to comply with relevant British Standards and Codes of Practice in respect of materials and workmanship, and site procedure and organisation, and specifically with BS 8000-0:2014.
5. If in doubt - ask!

TOWER - CRENELLATION TO SOUTH PARAPET

TOWER - SOUTH PARAPET

TOWER - CRENELLATION TO WEST PARAPET



TOWER - SOUTH WEST BROACH

Item 7.7 repoint defective pointing; allow to remove both stones and reinstate on removing elder roots



TOWER - SOUTH EAST BROACH

Items 7.9, 7.9.1 allow to carefully take down all outer casing stones; remove all elder roots; consolidate substrate and rebuild and repoint



TOWER - NORTH EAST BROACH

Items 7.10 rake out all defective pointing to flashing including all the way back to the door and repoint

drawing title		ASHLEY COURTNEY RIBA AABC ARCHITECT				
PHOTOS IDENTIFYING PROPOSED WORKS		36 Roseford Road, Cambridge CB4 2HD tel: 01223 750610 email: ac@ashleycourtney.co.uk				
client	job title	scale	date	job no.	dwg no.	rev
COTON PCC	URGENT REPAIRS	NTS	NOV 2020	20-27	02	